Riverdale Municipality invites tenders for removal and disposal of six (6) trees (three trees are identified as class 10, and three trees are identified as class 31) through the Dutch Elm Disease Maintenance Program. Only trees on the specified list will be reimbursed for removal, a copy of this list can be obtained from the municipal office.

Trees must be removed flush with the ground to the soil line, with no bark remaining.

- Equipment used to cut trees must be disinfected with methyl hydrate before servicing other healthy elms.
- Contractor is responsible to ensure wood from removed elms is chipped or destroyed right away, and in accordance with the legislation.
- Contractor is responsible to grind the stump to below ground level.
- Contractor is responsible for removing all debris and ensuring the site is clean after removal.
- Contractor will be responsible for all remediation if damage occurs to the property.

Contractor must comply with the Forest Health Protection Act, Dutch Elm Disease Maintenance Program, and all other regulations and legislation. The municipality is not responsible for any damage that might occur during the removal of trees.

Removal of all trees and debris must be complete and ready for final inspection prior to December 31st, 2026. Contractor is responsible to communicate with the Operations Manager prior to commencement of work.

Please have your tender enclosed in a sealed envelope labelled “Dutch Elm Tree Removal Tender” and delivered to the municipal office prior to November 26th, 2026 by 4:30 pm.

Riverdale Municipality
Attention: Darrel Link
670 2nd Ave
PO Box 520
Rivers, MB
R0K 1X0

If you have any further questions please contact Darrel Link, Operations Manager, 204-328-5300